



beaverfloorcare

COMPANY NAME : BEAVER FLOORCARE
CLIENT : APPLE
SITE : APPLE, NEW STREET BIRMINGHAM
ACTIVITY : STONE FLOOR MAINTENANCE & RE-SEALING

DATE OF RISK ASSESSMENT : 8th November 2017
AUTHOR : D.CAMPTON

| Key to Assessment | LOW Minor Impact Damage quickly repaired | MEDIUM Moderate Impact Partial Loss of Operations | HIGH Disaster Very Serious Consequences |
|-------------------|--|---|---|
|-------------------|--|---|---|

| HAZARD | PERSONS/PROPERTY AT RISK | CONTROLLED RISK | SUMMARY OF PROTECTIVE & PREVENTIVE MEASURES |
|--|---|-----------------|--|
| Slips , Trips and Falls during restoration activities (No heights or ladder work undertaken) | Beaver Personnel Site Personnel | LOW | <ul style="list-style-type: none"> • Work scheduled outside of trading times. • Extensive Staff Training in restoration/ cleaning techniques • Training in Site Housekeeping • Need for working in manageable areas • Avoidance of trailing cables etc • Use of Hazard Warning Signage at all times • Areas cordoned off as required - barriers, barrier tape, signs • Spill procedures established • Safety footwear worn by technicians |
| Use of Cleaning Chemicals - skin problems - eye contamination - inhalation of chemical vapours | Beaver Personnel Site Personnel Building Fabric | LOW | <ul style="list-style-type: none"> • Training provided in chemical use. • Use of non-hazardous chemicals whenever possible • Special Training in use of all Sealant products • Dispenser pumps , gloves used to prevent skin contact • PPE to be used - masks, glasses, gloves ,protective clothing • Protective masking to areas wherever required • Eye Wash in First Aid Kits carried on Site. |



COMPANY NAME : BEAVER FLOORCARE
CLIENT : APPLE
SITE : APPLE, NEW STREET BIRMINGHAM
ACTIVITY : STONE FLOOR MAINTENANCE & RE-SEALING

DATE OF RISK ASSESSMENT : 8th November 2017
AUTHOR : D.CAMPTON

| Key to Assessment | LOW Minor Impact Damage quickly repaired | MEDIUM Moderate Impact Partial Loss of Operations | HIGH Disaster Very Serious Consequences |
|-------------------|---|--|--|
|-------------------|---|--|--|

| HAZARD | PERSONS/PROPERTY AT RISK | CONTROLLED RISK | SUMMARY OF PROTECTIVE & PREVENTIVE MEASURES |
|---|--------------------------------------|-----------------|--|
| Musculoskeletal Disorders - Transporting cleaning equipment - Moving furniture at site - Using cleaning/reprocessing equpt - Working awkwardly e.g. on knees | Beaver Personnel | LOW | <ul style="list-style-type: none"> • Training in Manual Handling to ensure correct lifting of cleaning equipment, furniture etc. • Use of provided wheels to assist with furniture moving. • Training in correct use of cleaning machinery -e.g height etc adjustment of rotary machines to ensure no torque • Regular checks to machines including vibration etc • Try to avoid awkward working , if not , ensure adequate rest periods. Knee pads provided. • Safety shoes worn by staff to prevent foot damage. |
| Electrical Hazards - shocks | Beaver Personnel Site Premises | LOW | <ul style="list-style-type: none"> • Machinery used with RCD's to prevent electrocution, shocks & any interruption to supply • Staff trained in the safe use of electrical equipment • Regular PAT Testing & checks in accordance with Provision & Use of Equipment at Work Regs. 1998 • Masking to supply points and data ports. |
| Noise | Beaver Personnel | LOW | <ul style="list-style-type: none"> • Noise levels monitored - ear plugs provided |
| Damage to Site | Site Premises Fixtures & Fittings | LOW | <ul style="list-style-type: none"> • Filtration to sedimentation tanks to prevent suspended calcium deposits from blocking drains • All due care and protective measures taken to ensure no splashing or impact damage to fixtures & fittings • Extra care and protective measures to be taken when working to ensure no splashing or damage to floor |