

## **METHOD STATEMENT**

Process: STONE FLOOR MAINTENANCE - DEEP CLEANING

Site: APPLE STORE R545 – DRAKE CIRCUS PLYMOUTH

Operations Director: Thomas Campton Site Supervisor: Owyn Parrott

<u>Originator</u>: D.Campton <u>Position</u>: Director <u>Date</u>: 1<sup>st</sup> February 2018

H & S Representative

This method statement is critical to the health and safety of the activity it relates to. It is to be strictly adhered to. Any deviation must first be authorised by the Site Supervisor.

Specified Area: Sales Floor

Access: Monday 12<sup>th</sup> to Wednesday 14<sup>th</sup> February 2018 (2 nights)

Monday - Wednesday - from 18.00 pm to 06.00 am

Working Environment and Restrictions Health & Safety, Security & Fire Regulations in

accordance with our policies and site requirements

**Protection of Others**: Work to be undertaken at times requested by client. Areas

to be isolated & cordoned off as required

**Emergency Procedures:** Emergency procedures in accordance with site requirements

Personal Protective Equipment: Safety footwear, Safety Glasses, Gloves, Masks, Ear Plugs

Barrier cream , Protective Coveralls

Plant and Equipment: Specialised Rotary Floor Machines, Klindex Levighators,

Hercules, Fein Machine, Scrubber Driers (Battery & mains), Wet Vacuums, Tub Vacuums . Sundry cleaning

items.

All equipment PAT Tested , maintained regularly & used with RCD's.

Materials Handling/Storage and Safety Information: No special procedures required

Disposal in accordance with MSDS

**Stages:** ( to be undertaken in correct sequence):

- 1. Make contact with Security, park as required and adhere to Midsummer Place Shopping Centre requirements
- 2. Check in using IVR System / Site Representative
- 3. Cordon off areas, position hazard Warning Signage.
- 4. Remove shelves from 3<sup>rd</sup> party shelving areas if required and reposition tables /stools using Custom Wheels.
- 5. Mask areas as required to protect from splashes and any impact damage
- 6. Remove trims from power & data outlets and mask off.









- 7. **1**st **Night** Photograph areas (Left ,Right & Centre) after protection installed to show condition of areas to be processed.
- 8. Sweep / vacuum area to be processed, to remove dirt, debris and grit.
- 9. Deep Cleaning to all areas
- 10. After Final Rinse allow to dry.
- 11. Replace furniture as specified by floor plan
- 12. Remove all masking, equipment and products from site.- ensuring no items left on site.
- 13. Clean & check all areas to enable trading to commence.
- 14. 1st Night Photograph areas (Left ,Right & Centre) after areas processed
- 15. Contact Security to notify them work completed & comply with signing out procedures.

## 12th & 13th FEBRUARY 2018

**MALLSIDE** 

When Deep Cleaning the Apple floor adjacent to the Mall the procedure will be the same as at **– Stages 5 to10** but with extra masking to the Mall floor and placing of special protection. After works completed and cleaned , the area to be inspected and signed off by our Supervisor

N.B. Access to a water supply is vital to enable works to proceed All rubbish to be removed from site



