







COMPANY NAME: BEAVER FLOORCARE

CLIENT: APPLE

SITE: APPLE R136 TRAFFORD CENTRE

ACTIVITY: STONE FLOOR MAINTENANCE & RE-FINISHING

DATE OF RISK ASSESSMENT: 27th September 2017

AUTHOR: D.CAMPTON

Key to Assessment	LOW Minor Impact Damage quickly repaired	MEDIUM Moderate Impact Partial Loss of Operations	HIGH Disaster Very Serious Consequences
HAZARD	PERSONS/PROPERTY AT RISK	CONTROLLED RISK	SUMMARY OF PROTECTIVE & PREVENTIVE MEASURES
Slips , Trips and Falls during restoration & maintenance activities (No heights or ladder work undertaken)	Beaver Personnel Site Personnel	LOW	 Work scheduled outside of trading times. Extensive Staff Training in restoration/ cleaning techniques Training in Site Housekeeping Need for working in manageable areas Avoidance of trailing cables etc Use of Hazard Warning Signage at all times Areas cordoned off as required - barriers, barrier tape, signs Spill procedures established Safety footwear worn by technicians
Use of Cleaning Chemicals - skin problems - eye contamination - inhalation of chemical vapours	Beaver Personnel Site Personnel Building Fabric	LOW	 Training provided in chemical use. Use of non-hazardous chemicals whenever possible Special Training in use of Ardex R65P Dispenser pumps, gloves used to prevent skin contact PPE to be used - masks, glasses, gloves, protective clothing Protective masking to areas wherever required Eye Wash in First Aid Kits carried on Site.

Restoration and Maintenance of Carpet, Marble, Vinyl, Rubber and Wood

Reg. Office The Barn, Oldberrow Manor, Ullenhall Lane, Ullenhall, Warwickshire B95 5PF Tel: 01564 742095 Fax: 01564 742853

Beaver Floorcare Ltd.: Registered in England No. 6695922 info@beaverfloorcare.co.uk www.beaverfloorcare.co.uk www.beaverfloorcare.co.uk



Key to Assessment



LOW



MEDIUM



COMPANY NAME: BEAVER FLOORCARE CLIENT:

APPLE

SITE: APPLE R136 TRAFFORD CENTRE

ACTIVITY: STONE FLOOR MAINTENANCE & RE-FINISHING DATE OF RISK ASSESSMENT: 27th September 2017

HIGH

AUTHOR: D.CAMPTON

ito y to ricoccomoni		2510111	
	Minor Impact Damage quickly repaired	Moderate Impact Partial Loss of Operations	Disaster Very Serious Consequences
HAZARD	PERSONS/PROPERTY	CONTROLLED RISK	SUMMARY OF PROTECTIVE & PREVENTIVE
	AT RISK		MEASURES
Musculoskeletal	Beaver Personnel	LOW	Training in Manual Handling to ensure correct
Disorders	200.0.7 0.00		lifting of cleaning equipment, furniture etc.
5.00.40.0			Use of provided wheels to assist with furniture moving.
- Transporting cleaning equipment			Training in correct use of cleaning machinery -e.g height etc
- Moving furniture at site			adjustment of rotary machines to ensure no torque
- Using cleaning/reprocessing equpt			Regular checks to machines including vibration etc
- Working awkwardly e.g. on knees			Try to avoid awkward working , if not , ensure adequate
			rest periods. Knee pads provided.
			Safety shoes worn by staff to prevent foot damage.
			durity shoes worn by stail to prevent root damage.
Electrical Hazards	Beaver Personnel	LOW	Machinery used with RCD's to prevent electrocution, shocks &
- shocks	Site Premises		any interruption to supply
	one i remises		Staff trained in the safe use of electrical equipment
			Regular PAT Testing & checks in accordance with
			Provision & Use of Equipment at Work Regs. 1998
			Masking to supply points and data ports.
Voise	Beaver Personnel	LOW	Noise levels monitored - ear plugs provided
Damage to Site / Mall	Site Premises	LOW	Filtration to sedimentation tanks to prevent suspended calcium
	Fixtures & Fittings		deposits from blocking drains
			All due care and protective measures taken to ensure no
			splashing or impact damage to fixtures & fittings
			Extra care and protective measures to be taken when working
			Mallside to ensure no splashing or damage to Mall floor
			Mallside area to be inspected & signed off by Supervisor
			when works completed.