







COMPANY NAME:

BEAVER FLOORCARE CLIENT: **NORLAND MANAGED SERVICES** SITE: **ACTIVITY:**

KPMG SNOW HILL BIRMINGHAM

LIMESTONE RESTORATION

DATE OF RISK ASSESSMENT: 7th February 2018 AUTHOR: D Campton

Key to Assessment	LOW Minor Impact Damage quickly repaired	MEDIUM Moderate Impact Partial Loss of Operations	HIGH Disaster Very Serious Consequences
HAZARD	PERSONS/PROPERTY AT RISK	CONTROLLED RISK	SUMMARY OF PROTECTIVE & PREVENTIVE MEASURES
Slips , Trips and Falls during restoration & maintenance activities (No heights or ladder work undertaken)	Beaver Personnel Site Personnel Members of the Public	LOW	 Work to be carried out at weekends Extensive Staff Training in restoration/ cleaning techniques Training in Site Housekeeping Need for working in manageable areas Avoidance of trailing cables etc Use of Hazard Warning Signage at all times Areas cordoned off as required - barriers, barrier tape, signs Stairways & Lifts to be taken out of operation, cordoned off with appropriate signage whilst being restored or to restrict access to other areas being processed. Spill procedures established Safety footwear worn by technicians
Use of Cleaning Chemicals - skin problems - eye contamination - inhalation of chemical vapours	Beaver Personnel Site Personnel Members of the Public Building Fabric	LOW	 Training provided in chemical use, incl.dilution rates Use of non-hazardous chemicals whenever possible Dispenser pumps, gloves used to prevent skin contact PPE to be used - masks, glasses, gloves, protective clothing Protective masking to areas wherever required Extra care in use of resin in accordance with COSHH Eye Wash in First Aid Kits carried on Site. Adequate Ventilation required due to vapours from resin









COMPANY NAME:

CLIENT : SITE : ACTIVITY : BEAVER FLOORCARE
NORLAND MANAGED SERVICES
KPMG SNOW HILL BIRMINGHAM
LIMESTONE RESTORATION

DATE OF RISK ASSESSMENT: 7th February 2018

AUTHOR: D Campton

Key to Assessment	LOW Minor Impact Damage quickly repaired	MEDIUM Moderate Impact Partial Loss of Operations	HIGH Disaster Very Serious Consequences
HAZARD	PERSONS/PROPERTY AT RISK	CONTROLLED RISK	SUMMARY OF PROTECTIVE & PREVENTIVE MEASURES
Musculoskeletal Disorders - Transporting cleaning equipment - Moving furniture at site - Using cleaning/reprocessing equpt - Working awkwardly e.g. on knees	Beaver Personnel	LOW	 Training in Manual Handling to ensure correct lifting of cleaning equipment, furniture etc. Heavy loads to be avoided if cannot be lifted safely Training in correct use of cleaning machinery -e.g height etc adjustment of rotary machines to ensure no torque Regular checks to machines including vibration etc Try to avoid awkward working, if not, ensure adequate rest periods. Knee pads provided. Safety shoes worn by staff to prevent foot damage.
Electrical Hazards - shocks	Beaver Personnel Site Premises	LOW	 Machinery used with RCD's to prevent electrocution, shocks & any interruption to supply Staff trained in the safe use of electrical equipment Regular PAT Testing & checks in accordance with Provision & Use of Equipment at Work Regs. 1998
Noise	Beaver Personnel	LOW	Noise levels monitored - ear plugs provided
Waste Water Filtration & Disposal	Site Premises	LOW	Installation of additional filtration to sedimentation tanks to prevent suspended calcium deposits from blocking drains