







COMPANY NAME : BEAVER FLOORCARE

CLIENT: APPLE

SITE: APPLE R153 MEADOWHALL SHEFFIELD ACTIVITY: BACK OF HOUSE FLOOR TREATMENT

DATE OF RISK ASSESSMENT: 19th December 2017

AUTHOR: D.CAMPTON

| Key to Assessment | LOW Minor Impact | MEDIUM Moderate Impact | HIGH Disaster |
|--|---|----------------------------|--|
| | Damage quickly repaired | Partial Loss of Operations | Very Serious Consequences |
| HAZARD | PERSONS/PROPERTY AT RISK | CONTROLLED RISK | SUMMARY OF PROTECTIVE & PREVENTIVE MEASURES |
| Slips , Trips and Falls during restoration & maintenance activities (No heights or ladder work undertaken) | Beaver Personnel Site Personnel | LOW | Work scheduled outside of trading times. Extensive Staff Training in restoration/ cleaning techniques Training in Site Housekeeping Need for working in manageable areas Avoidance of trailing cables etc Use of Hazard Warning Signage at all times Areas cordoned off as required - barriers, barrier tape, signs Spill procedures established Safety footwear worn by technicians |
| Use of Cleaning Chemicals - skin problems - eye contamination - inhalation of chemical vapours | Beaver Personnel Site Personnel Building Fabric | LOW | Training provided in chemical use. Use of non-hazardous chemicals whenever possible Special Training in use of sealing chemicals Dispenser pumps, gloves used to prevent skin contact PPE to be used - masks, glasses, gloves, protective clothing Protective masking to areas wherever required Eye Wash in First Aid Kits carried on Site. |









COMPANY NAME:

Key to Assessment

CLIENT:

ACTIVITY:

SITE:

BEAVER FLOORCARE

APPLE

APPLE R153 MEADOWHALL SHEFFIELD

LOW **Minor Impact**

BACK OF HOUSE FLOOR TREATMENT

DATE OF RISK ASSESSMENT: 19th December 2017 AUTHOR: D.CAMPTON

| MEDIUM | HIGH |
|-----------------|----------|
| Moderate Impact | Disaster |

| | Damage quickly repaired | Partial Loss of Operations | Very Serious Consequences |
|---|--------------------------------------|----------------------------|--|
| HAZARD | PERSONS/PROPERTY | CONTROLLED RISK | SUMMARY OF PROTECTIVE & PREVENTIVE |
| | AT RISK | | MEASURES |
| Musculoskeletal Disorders - Transporting cleaning equipment - Moving furniture at site - Using cleaning/reprocessing equpt - Working awkwardly e.g. on knees | Beaver Personnel | LOW | Training in Manual Handling to ensure correct lifting of cleaning equipment, furniture etc. Use of provided wheels to assist with furniture moving. Training in correct use of cleaning machinery -e.g height etc adjustment of rotary machines to ensure no torque Regular checks to machines including vibration etc Try to avoid awkward working, if not, ensure adequate rest periods. Knee pads provided. |
| Electrical Hazards - shocks | Beaver Personnel Site Premises | LOW | Safety shoes worn by staff to prevent foot damage. Machinery used with RCD's to prevent electrocution, shocks & any interruption to supply Staff trained in the safe use of electrical equipment Regular PAT Testing & checks in accordance with Provision & Use of Equipment at Work Regs. 1998 Masking to supply points and data ports. |
| Noise | Beaver Personnel | LOW | Noise levels monitored - ear plugs provided |
| Damage to Site | Site Premises Fixtures & Fittings | LOW | All due care and protective measures taken to ensure no splashing or impact damage to fixtures & fittings Extra care and protective measures to be taken when working on all surfaces |

Restoration and Maintenance of Carpet, Marble, Vinyl, Rubber and Wood